

Soil Erosion and Sediment Control Plan

Consistent with Standard 3 of this Manual, project proponents must develop and implement a Soil Erosion and Sediment Control (SESC) Plan in accordance with local and/or state regulatory requirements, the [Connecticut Guidelines for Soil Erosion and Sediment Control Guidelines](#), as amended (Guidelines), and the requirements of the CTDEEP General Permit for the Discharge of Stormwater and Dewatering Wastewaters from Construction Activities. The SESC Plan should, at a minimum, demonstrate the methods and designs to be utilized during construction and stabilization of the site following completion of construction activity. Erosion and sediment control measures should be included on the plans with sufficient detail to facilitate review of the design by the reviewing authority and proper construction of the measures.