

Standard 3 – Construction of Soil Erosion and Sediment Control

Effective soil erosion and sedimentation control measures should be designed, installed, and maintained during construction and land disturbance activities. Project proponents must develop and implement a Soil Erosion and Sediment Control (SESC) Plan in accordance with local and/or state regulatory requirements, the [Connecticut Guidelines for Soil Erosion and Sediment Control](#), as amended (Guidelines), and the requirements of the CTDEEP General Permit for the Discharge of Stormwater and Dewatering Wastewaters from Construction Activities. The SESC Plan documents how the proposed activities are consistent with the performance criteria in the Guidelines. The SESC Plan should be included as part of the Stormwater Management Plan (see [Chapter 12](#)).